

Invitation to Bid



Title: CN / EJ&E - Matteson Connection Contract No. 3

From: LONNIE SCHULTZ, HARBOUR CONTRACTORS, INC.
(815) 254-5500

Bids Due: 08/04/2010 at 5:00 PM

Project Details

Project Title: CN / EJ&E - Matteson Connection Contract No. 3

Type & Structure: New, Utilities

Status: General Contract Bidding

Location: CN Rail Line in Matteson / Park Forest
Matteson, IL 60443

Bids Due: 08/04/2010 at 5:00 PM

Requirements: Labor Type: Union

Scope of Work: Project Name: CN/EJ&E Matteson Connection Contract No. 3

Subcontractor Bids Due: By Close of Business on Wednesday, August 4th

() **** Yes, We Will Bid. We will down load plans at Harbours ftp:// plan room site.

WEB LINK: <http://harbour.ftpstream.com/?lid=jg1f123f>

Or

FTP: <ftp://pubbid:hcibidder@harbour.ftpstream.com>

Folder: 25-1007-04_CN_Matteson_Connection_3

Username: pubbid Password: hcibidder

() **** Yes, We Will Bid. Please FedEx / UPS / DHL CD File of plans & specifications.

FedEx Account # _____ UPS Account # _____

() **** We are bidding and already have bidding documents.

() **** Will not Bid.

Please update the contact information that you would like future invitations and addendums to be sent to

Company Name: _____

Contact Name: _____

Trade Bidding: _____

E-Mail Address: _____

Address: _____

Phone #: _____

Fax #: _____

Bid Notes: Harbour Contractors, Inc. invites you to Bid to furnish all labor, materials, equipment and incidentals required for the CN Matteson Connection No. 3 project located in Matteson, Illinois. Please return this invite with your full info filled out including e-mail so that we are able to contact you with any addendums or additional information. Bid Scope:

Item No.	Description	Quantity	Unit
	SITE WORK		
1	NITROGEN FERTILIZER NUTRIENT	1,498	LB

2	PHOSPHORUS FERTILIZER NUTRIENT	1,498	LB	
3	POTASSIUM FERTILIZER NUTRIENT	1,498	LB	
4	EARTH EXCAVATION	183,000	CY	
5	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (5% of Excavation)			9,150 CY
6	TRENCH BACKFILL	100	CY	
7	TOPSOIL EXCAVATION AND PLACEMENT	17,900	CY	
8	TOPSOIL FURNISH AND PLACE, 6	11,400	SY	
9	SEEDING CLASS 2A	0.18	AC	
10	SEEDING - WET MESIC TALL GRASS PRAIRIE	0.86	AC	
11	SEEDING - MESIC TALL GRASS PRAIRIE	15.6	AC	
12	MULCH, METHOD 1	889	SY	
13	EROSION CONTROL BLANKET	79,670	SY	
14	PERIMETER EROSION BARRIER	14,111	LF	
15	PERIMETER EROSION BARRIER REMOVAL	3,639	LF	
16	STONE RIPRAP, CLASS A1	140	TN	
17	STONE RIPRAP, CLASS A3	640	TN	
18	STONE RIPRAP, CLASS A4	211	TN	
19	STONE RIPRAP, CLASS A5	258	TN	
20	SUB-BASE GRANULAR MATERIAL, TYPE B	541	CY	
21	HOT-MIX ASPHALT BASE COURSE, 5	2,306	SY	
22	BITUMINOUS MATERIALS (PRIME COAT)	1,153	GAL	
23	HOT-MIX ASPHALT BINDER COURSE, IL 12.5, N50	199	TN	
24	HOT-MIX ASPHALT SURFACE COURSE, MIX D, N70	194	TN	
25	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 IN	87	SY	
26	PORTLAND CEMENT CONCRETE SIDEWALK, 5 IN	3,356	SF	
27	PAVEMENT REMOVAL	2,244	SY	
28	DRIVEWAY PAVEMENT REMOVAL	228	SY	
29	COMBINATION CURB AND GUTTER REMOVAL	1,590	LF	
30	SIDEWALK REMOVAL	2,872	SF	
31	MEDIAN REMOVAL	1,298	SF	
32	PIPE CULVERT REMOVAL	217	LF	
33	PRECAST REINF. CONC. FLARED END SECTIONS, 12			3 EA
34	PRECAST REINF. CONC. FLARED END SECTIONS, 15			2 EA
35	PRECAST REINF. CONC. FLARED END SECTIONS, 24			3 EA
36	PRECAST REINF. CONC. FLARED END SECTIONS, 30			6 EA
37	PRECAST REINF. CONC. FLARED END SECTIONS, 36			13 EA
38	PRECAST REINF. CONC. FLARED END SECTIONS, 42			4 EA
39	PIPE CULVERTS, TYPE 2, RCCP, CL III, 12	26	LF	
40	PIPE CULVERTS, TYPE 2, RCCP, CL IV, 15	62	LF	
41	PIPE CULVERTS, TYPE 2, RCCP, CL IV, 24	88	LF	
42	PIPE CULVERTS, TYPE 2, RCCP, CL IV, 36	111	LF	
43	STORM SEWERS, TYPE 2, RCCP, CL V, 12			96 LF
44	PIPE CULVERTS, TYPE 2, RCCP, CL V, 30	232	LF	
45	PIPE CULVERTS, TYPE 2, RCCP, CL V, 36	603	LF	
46	PIPE CULVERTS, TYPE 2, RCCP, CL V, 42	257	LF	
47	PIPE UNDERDRAIN, FABRIC LINED TRENCH 8	135	LF	
48	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	1		EA
49	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	1		EA
50	MANHOLES, TYPE A, 6' DIAMETER, TYPE 1 FRAME, OPEN LID	1		EA
51	INLET, TYPE A, 2' DIAMETER, OPEN LID	0		EA
52	DRAINAGE STRUCTURES TO BE ADJUSTED	5		EA
53	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	18		EA
54	FILLING DRAINAGE STRUCTURES	1		EA
55	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	1,574	LF	
56	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	57	LF	
57	CONCRETE MEDIAN, TYPE SB-6.12	1,196	SF	
58	CORRUGATED MEDIAN	392	SF	
59	CHAIN LINK FENCE, 8'	445	LF	
60	CHAIN LINK GATES, 8' x 16' DOUBLE	1		EA

61	CHAIN LINK FENCE REMOVAL	430	LF	
62	SPECIAL WASTE DISPOSAL	1,500	CY	
63	BTEX-PNAS SOIL ANALYSIS	10	EA	
64	BTEX-PNAS GROUNDWATER ANALYSIS		10	EA
65	RCRA METALS TCLP SOIL ANALYSIS		15	EA
66	RCRA METALS GROUNDWATER ANALYSIS		15	EA
67	SIGN PANEL TYPE 1	160	SF	
68	METAL POST TYPE B	100	LF	
69	REMOVE CONCRETE FOUNDATION - GROUND MOUNT		1	LSUM
70	PAINT PAVEMENT MARKING LINE, 4	1,150	LF	
71	WOODEN FENCE REMOVAL & REPLACEMENT	227	LF	
72	STABILIZED CONSTRUCTION ENTRANCE	1,000	SY	
73	MAINTAIN EXISTING EROSION CONTROL MEASURES		12	MONTH
74	TRAFFIC CONTROL AND PROTECTION FOR DETOUR ROUTE		1	LSUM
75	20 CY DUMPSTER	50	EA	
76	SIGN REMOVAL		1	LSUM
77	CLEARING & GRUBBING	4	ACRE	
78	CONTROL STRUCTURE, 5' DIAMETER, CLOSED LID		2	EA
79	ABANDON EXISTING CULVERT	1	EA	
80	GEOTEXTILE FABRIC FOR RAILROAD CROSSING	240	SY	
	STRUCTURAL WORK			
81	NOISE ABATEMENT WALL	28,660	SF	
82	RETAINING WALL E (SE CONNECTION)		1	LSUM
	TRACK WORK			
83	CONSTRUCT CWR TRACK - WOOD TIES	8,565	TF	
84	CONSTRUCT CWR TRACK - CONCRETE TIES	4,895	TF	
85	CONSTRUCT CWR TRACK - TRANSITION TIES	280	TF	
86	INSTALL NO 10 TURNOUTS (PANEL)	6	EA	
87	INSTALL NO 12 TURNOUTS (PANEL)	12	EA	
88	INSTALL NO 15 TURNOUTS (PANEL)	4	EA	
89	INSTALL TRACK FIELD WELDS	300	EA	
90	REALIGN TRACK	2,593	TF	
91	INSTALL CONCRETE CROSSING PANELS	0	FT	
92	INSTALL TIMBER CROSSING PANELS	384	FT	
93	INSTALL RUBBER CROSSING PANELS	152	FT	
94	INSTALL TIMBER TIE TRACK PANEL, 80 LF		3	EA
95	REMOVE TRACK	19,873	TF	
96	REMOVE TURNOUTS		21	EA
97	SUBBALLAST	15,517	CY	
98	INSTALL HOT AIR BLOWERS - BY OTHERS - NIC		13	EA
99	INSTALL RAIL LUBRICATOR - BY OTHERS - NIC		6	EA
100	INSTALL INSULATED PLUGS		78	EA
101	CREDIT FOR TRACK MATERIAL RECLAIM		1	LSUM
	MISCELLANEOUS			
102	FLAGGERS	240	MAN-DAY	
103	RAILROAD SIGNAL IMPROVEMENTS - PER INTERLOCKING		3	EA
104	GRADE CROSSING SIGNAL IMPROVEMENTS		1	LSUM
	OWNER ALTERNATES			
ALT 1A	UNLOAD TURNOUTS		EA	
ALT 2A	UNLOAD GONDOLA OF PREPLATED WOOD CROSSTIES		EA	
ALT 3A	UNLOAD GONDOLA CARLOAD OF OTHER TRACK MATERIALS		EA	
ALT 4A	UNLOAD STRING/RIBBON OFCONT. WELDED RAIL FROM RAIL TRAIN		EA	
ALT 5A	UNLOAD PALLET OF OTHER TRACK MATERIAL		EA	

Categories Required

019505- Associations

014529- Testing Laboratories	321100- Sand & Gravel
014530- Testing Laboratories (DBE,WBE)	321123- Aggregates--Lightweight
021020- Surveyors (DBE,WBE)	321125- Sand & Gravel (DBE,WBE)
022113- Surveyors	321140- Paving Materials (DBE,WBE)
030120- Concrete Contrs.--Reinforced Concrete	321540- Stone--Crushed
033000- Concrete--Ready Mixed	321723- Pavement Markings
033500- Concrete Contrs.--Sidewalks/Floors/Curbs	323100- Fences
034500- Concrete--Precast-Arch. & Struct.	323130- Fence Contractors (DBE,WBE)
037000- Foundation Contractors	323200- Retaining Wall Systems
038220- Concrete Contractors (DBE,WBE)	323250- Retaining Walls (DBE,WBE)
310100- Excavating Contractors	323516- Noise Barriers-Highway
310140- Shoring Contractors	329119- Topsoil
310160- Pile Driving Contractors	329200- Landscape Materials & Equipment
310165- Pile Driving Contractors (DBE,WBE)	329230- Landscape Materials & Equip. (DBE,WBE)
310175- Excavating Contractors (DBE,WBE)	330100- Underground Utilities--Contractors
311000- Site Development	330105- Sewer-Watermain-Utilities (DBE,WBE)
311300- Tree Service	330110- Water Main Construction
312323- Fill & Backfill	330130- Sewer Contractors
312500- Soil Erosion Control	330516- Concrete--Precast-Sanitary, Drainage
312570- Soil Erosion Control (DBE,WBE)	334000- Pipe--Clay
313200- Soil Stabilization	334213- Pipe--Concrete
315000- Shores & Shoring	334616- Pipe--Footing & Underdrain
316200- Piling	344100- Traffic Control Systems & Devices
320100- Paving Contractors	347100- Road Construction--Heavy & Highway
320190- Landscape Construction	347115- Paving & Road Construction (DBE,WBE)
320195- Landscape Contractors (DBE,WBE)	347200- Railroad Track Construction
321100- Paving Materials	

Internet Access to Plans, Specifications and Bid Documents



[Go to BB-Bid Online Plan Room](#) - Free Viewing and Downloading



[CN/EJ&E Matteson Connection Contract No. 3](#)

Notes: Username: pubbid
Password: hcibidder

Locations of Plans, Specifications and Bid Documents

HARBOUR CONTRACTORS, INC.

LONNIE SCHULTZ (CHIEF ESTIMATOR)
23830 W. MAIN STREET
PLAINFIELD, IL 60544
Phone: (815) 254-5500
Fax: (815) 254-5505



CONTRACTORS REGISTER, INC.

JEFFERSON VALLEY, NY 10535 · (800) 431-2584 FAX: (914) 243-0287
WWW.THEBLUEBOOK.COM · EMAIL: INFO@THEBLUEBOOK.COM
PRIVACY POLICY · TERMS OF USE · SITE MAP
COPYRIGHT © 2010 CONTRACTORS REGISTER, INC.